

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for MONTMORENCY (County), Located In: VIENNA TWP., Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

RECEIVED MONTMORENCY COUNTY REGISTER OF DEEDS Dec 23 2 59 PM '93 A. PANGEN-MOELLROY

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

I, Frederick J. King, in a field survey on August - September, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5 SW Cor Sec 7 & NW Cor Sec 18, T.30 N., R.1 E. Orig. Post by John Hodges, D.S. - May 1839 S34°W-22 lks (14.52') Sugar N35°W-21 lks (13.86') Sugar 1979 - Act 132 Sur. by N. Caldwell Rec L.2, Pg 530 Does not indicate cor. evidence - No Wit. Act 74 Rec. Bk. 1, Pg. 253 by N. Caldwell - May 1979 Fnd 1/2" Bar in C.L. Rd. - S65°W-51.3'-20" W Pine S55°E-59.7'-30" Map - N52°W-32'96"-Conc. Mon. Act 74 Rec. Bk. 1, Pg. 285 by F. Bischer - Oct 1980 Fnd Rec 1/2" Bar - Same Wit. as N. Caldwell

A-6 West 1/4 Cor., Sec. 18, T.30 N., R.1 E. Orig. Post by John Hodges, D.S. - May 1839 S19°W-14 lks (9.24') Hemlock N34°W-14 lks (9.24') Hemlock 1979 - Act 132 Sur by N. Caldwell, Rec L. 2, Pg. 530 Does not indicate cor. evidence - No Wit. Act 74 Rec. Bk. 1, Pg. 252 by N. Caldwell - May 1979 Fnd 1/2" Bar in Mon Box East - 7.7' - C.L. Pvmt. N55°W-35.57' - Conc. Mon. S45°W-43.4' - NE Cor Stone Pillar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 SW Cor Sec 7 & NW Cor Sec 18, T.30 N., R.1 E. Fnd. Rec. 1/2" Iron (Bk 1, Pg. 253 & Pg 285) N.52°W. - 32.96' - Fnd. Rec. Conc. Mon. No other Caldwell or Bischer Witnesses Fnd. NO ORIGINAL CORNER EVIDENCE FOUND

A-6 West 1/4 Cor., Sec. 18, T.30 N., R.1 E. Fnd. Rec. 1/2" Iron in Mon. Box (Bk. 1, Pg. 252) East - 7.7' - C.L. of Pvmt. N55°W- 35.57' - Fnd. Conc. Mon. S45°W- 43.4' - NE Cor Stone Pillar NO ORIGINAL CORNER EVIDENCE FOUND

This Cor. is the STANDARD CORNER on the MICHIGAN MERIDIAN.

This Cor. is the STANDARD CORNER on the MICHIGAN MERIDIAN.

Approved by the Montmorency County Peer Review on Sept. 24, 1993, as the best available evidence of the position of the corner

Approved by the Montmorency County Peer Review on Sept. 24, 1993, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 SW Cor Sec 7 & NW Cor Sec 18, T.30 N., R.1 E. Placed Mon. Box - Set Mont. Co. Re-Mon Cap on Fnd Iron Cor. is 0.5' N. of C.L. of N-S Pvmt Cor. is 8' N of C.L. Rd to E (Brown Rd) N65°0E. - 47.64' - Set Tag S. Sd, Fnc Cor Post S.40°E. - 49.58' - Set Tag N. Sd. Fnc Cor Post S.80°W. - 37.49' - Set Tag N. Sd. 8" Maple N45°W. - 45.41' - Set Tag NE Sd. Fnc Post N.52°W. - 32.96' - Fnd Rec. Conc. Mon. SOUTH - 395.72' - Fnd RR Spk @ Cor M-5 T30N-R1W Set Treated R.T. Post @ NE Cor of Intersection

A-6 West 1/4 Cor., Sec. 18, T.30 N., R.1 E. Set Mont. Co. Re-Mon Cap on Fnd 1/2" Iron in Mon. Box Cor. is 7.7' N. of C.L. of N-S Pvmt. N.65°E. - 96.88' - Set Tag S. Sd. 12" Elm S.35°E. - 71.84' - Set Tag NE Sd. No Gate Post S.40°W. - 40.92' - Set Tag SE Sd. Pwr. Pole S.45°W. - 43.4' - NE Cor. Stone Pillar (Rec) N65°W. - 25.47' - Set Tag NE Sd. 3" Elm N.55°W. - 35.57' - Conc. Mon. (Rec) SOUTH - 360.97' - Fnd 1/2" Iron @ Cor. M-6 T30N-R1W Set Treated R.T. Post on E. Sd. Rd., Opp. Cor.

NOTE: All witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King Date Dec. 23, 1993 Surveyor's Michigan License No. 25852

