

MAY 18 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTMORENCY
(County)

Located in: VIENNA TWP Corner Code -##

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:05:22

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 30N R 1E D-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 13, column C.

I, FREDERICK J. KING, in a field survey on May 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13 - SOUTH 1/4 CORNER OF SECTION 32

May 1839 - Original Post set by Clason, Dep. Sur. N52°W - 22 lks (14.52') 7" Spr Pine
N70°E - 22 lks (14.52') 6" Spr. Pine
Date ? - F.N. Smith #754 - Don Marlatt, P.S. #18660 provided map of area, indicating that Smith had worked in area and Peer Committee felt that he had set this corner - No Corner Description or Witnesses
No Act 74 Found Recorded for this Corner
No Act 132 Found Recorded for this Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 - SOUTH 1/4 CORNER OF SECTION 32

No Original Government Corner Evidence Found
Found Conc. Mon. @ Corner D-13
East - 49.02' - Found Axle Shaft @ Cor. D-1 (T29N-R1E)
N65°E - 8.1' - Found Spk in S. sd of 10" J. Pine
S40°W - 4.1' - Found Spk in SW sd of 8" J. Pine
N85°W - 25.2' - Found Spk in S. sd of 10" J. Pine
Corner D-13 is ± 43' N of C.L. of E-W Trail & ±80' W of C.L. N-S trail.

This corner was approved by County Peer Review on June 7, 1996 as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 - SOUTH 1/4 CORNER OF SECTION 32

Placed Montmorency County ReMon Cap on found Concrete Mon.
N65°E - 8.08' - Set S&T above found Spk - S sd 10" J. Pine
S35°E - 27.79' - Set S&T NE side 10" J. Pine
S40°W - 4.02' - Set S&T above found Spk SE side 8" J. Pine
N85°W - 25.14' - Set S&T above found Spk S. side 10" J. Pine
Corner is ± 43' N. of C.L. E-W Trail & ± 80' W. of C.L. N-S Trail



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

APPROVED BY PEER GROUP

Date October 24, 1996

JUN 07 96

L.H.B.