

MAY 1 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)

Located In: VIENNA TWP Corner Code #

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-06-1996 11:05:32

A. FANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 30N R 1E E-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I. FREDERICK J. KING, in a field survey on May 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 - CORNER COMMON TO SECTIONS 32 & 33 (Cor E-1 (29-1) Intersected 38 lks (25.08') E-13
May 1839 - Original Post set by Clason, Dep. Sur. N54°W - 21 lks (13.86') - 7" Spr Pin
N74°E - 36 lks (23.76') - 10" Spr Pin
Date? - F.N. Smith #754 - Don Marlatt, P.S.#18660 provided map of area, indicating that Smith had worked in area and Peer Committee felt that he had set this corner.
No Corner Description or Witnesses
No Act 74, found Recorded for this Corner
No Act 132 found Recorded for this Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 - CORNER COMMON TO SECTIONS 32 & 33
No Original Government Corner Evidence Found
Found Conc. Mon @ Corner E-13 East -25.21' - Found Axle Shaft @ Cor. E-1 (T29N-R1E) OGN - 38 lks (25.08') East of Cor E-1:
N75°E - 12.6' - Found Spk W. side of 10" J. Pine
South - 30.6' - Found Spk N. side of 12" J. Pine
N75°W - 43.5' - Found Spk E. side of 10" J. Pine
North - 41.4' - Found Spk W. side of 10" J. Pine
Corner E-13 is ±13' N. of C.L. of E-W Trail

This Corner Approved by County Peer Review on June 7, 1996m as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 - CORNER COMMON TO SECTIONS 32 & 33
Placed Montmorency County Re-Mon Cap on found Conc. Mon.
N75°E - 13.10' - Set S&T S. side of 10" J. Pine
South - 31.57' - Set S&T E. side of 12" J. Pine
N75°W - 43.91' - Set S&T S. side of 10" J. Pine
North - 41.41' - Set S&T above Spk found W. side of 10" J. Pine
Corner is ±13' N. of C.L. of E-W Trail
East - 25.21' - Corner E-1 (29-1)



Signed by Frederick J. King APPROVED BY PEER GROUP Date October 24, 1996

Surveyor's Michigan License No. 25852 JUN 07 96