

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Liber **00012** Page **0169**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MONTMORENCY
(County)

Located In: VIENNA TWP. Corner Code ##

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>30N</u> R <u>1E</u> | <u>F-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

11-14-1995 10:17:24

A. PANGAN-MCELROY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. King, in a field survey on May 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 - SOUTH 1/4 CORNER, SECTION 33

May 1839 - Original Post set by Clason, Deputy Surveyor - N.73°W. - 20.46' (31 lks) - Pine
 N.15°E. - 11.88' (18 lks) - Pine
 No Recorded Act 132 Found
 No Recorded Act 74 Found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 - SOUTH 1/4 CORNER, SECTION 33

Found Conc. Mon ± 8 1/2' North of E-W 2-track
 East - 28.53' - Found Axle Shaft @ Corner F-1, T29N-R1E
 Meas. from E-13 to F-13 - 2619.50'
 Meas. from F-13 to G-13 - 2619.00'

SURVEY &
 REMONUMENTATION

DEC 18 1995

COMMISSION

**APPROVED BY
 PEER GROUP**

JUN 02 95

[Signature]

This corner approved by Peer Review Committee on June 2, 1995, as the best available evidence of the re-establishment of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 - SOUTH 1/4 CORNER, SECTION 33

Set County Re-Mon Cap on Fnd Conc. Mon. N15°E - 87.35' - Set Tag W side 10" Oak
 S.75°E - 115.92' - Set Tag N side 10" Oak S20°E - 46.95' - Set Tag E side 10" Oak
 N.60°W - 26.87' - Set Tag S side 15" Oak
 Corner is ± 8 1/2' North of C.L. of E-W 2-track
 Corner F-1 is 28.53' East of Corner F-13
 Set 2"x4" Treated Stake - 20' North of Corner F-13



Signed by Frederick J. King

Date 10-30-95

Surveyor's Michigan License No. 25852