

**SURVEY &
REMONUMENTATION**

Montmorency County Remonumentation

DEC 18 1995

Libel **00012** Page **0170**

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MONTMORENCY</u> <small>(County)</small>	Located In: <u>VIENNA TWP.</u>	Corner Code <u>##</u> <u>G-13</u>
1. Public Land Survey	T <u>30N</u> R <u>1E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-14-1995 10:17:34

A. PANGAH-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. King, in a field survey on May 3, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 - CORNER COMMON TO SECTIONS 33 & 34

- May 1839 - Original Post set by Clason, Deputy Surveyor - N.21°W. - 23.10' (35 lks) - Y Pine
N.30°E. - 23.10' (35 lks) - Y Pine
- May 1976 - Act 74 by L. Beauregard, P.S.#18654, Recorded Bk.1, Pg. 166
States that 3" Monument Fnd, possibly set by F. Smith or G.F. De1-Mater
N.75°W. - 50.20' - 6" Maple
South - 68.10' - 10" Oak
East - 31.68' - Axle Shaft @ NW Cor., Sec.3, T29N-R1E
- June 1979 - Act 132 by L.G. Beauregard, P.S.#18654, Rec. L.2, Pg.539 - States Rec. Conc. Mon was Fnd.- Same

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 - CORNER COMMON TO SECTIONS 33 & 34

- No Corner Found - Appears to have been removed by pipeline activity.
- Set 1/2" iron, at Rec. 31.68' from Corner G-1, T29N-R1E & on line between Corners F-1 & G-1, T29N-R1E
South - ± 67.9' (R-68.10') - Fnd Blaze in Rec. 10" Oak (Now 18" Oak)
N.75°W. - 50.0' (R-50.2') - Fnd Blaze in Rec. 6" Maple (Now 10" Maple)
East - 31.68' - Found Rec. Axle Shaft @ Corner G-1, T29N-R1E.

**APPROVED BY
PEER GROUP**

JUN 02 95

[Signature]

This corner approved by Peer Review Committee on June 2, 1995 as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 - CORNER COMMON TO SECTIONS 33 & 34

- Set Conc. Mon & County Re-Mon Cap @ 1/2" Iron Location.
- N.85°E. - 83.54' - W face of Stop Sign Post
- South - 68.38' - Set Tag E side 18" Oak
- S.85°E. - 23.48' - Set Tag S side 24" Maple
- N.75°W. - 50.20' - Set Tag S side 10" Maple
- Corner is ± 34' West of West edge of N-S gravel road & ± 7' South of C.L. of E-W 2-track
- Corner G-1 is 31.68' East of Corner G-13
- Set 2"x4" Treated Stake alongside Corner G-13

Signed by Frederick J. King

Date 10-30-95

Surveyor's Michigan License No. 25852

