

DEC 18 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-14-1995 10:16:45

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

| | | |
|---------------------------------------|-----------------------------------|--------------------------------------|
| <u>MONTMORENCY</u> (County) | Located In: <u>VIENNA TWP.</u> | Corner Code <u>##</u> <u>K-13</u> |
| 1. Public Land Survey | T <u>30N</u> R <u>1E</u> | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Frederick J. King, in a field survey on June 1, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 - CORNER COMMON TO SECTIONS 35 & 36

- May 1839 - Original Post set by Clason, Deputy Surveyor - N42°W-17.16'-(26 lks) 18" Hem N24°E-16.50'-18" Hem
- June 1969- Survey by NC Caldwell- Fnd 4"x4" Post by F. Smith - N20°E-12.50'-6" Tw Brch
S85°E-17.80'-14" Ced Stmp - S85°E-49.35'-Conc Mon N70°E- 34.10'- Conc Mon
- Sept 1974- Act 132 by L. Beauregard, PS #18654 - K-13 ref in wit to Cor K-1 as S89°01'54"W-49.35' of Cor. K-1
Rec L.1, Pg. 600 to 4"x4" Post at Cor K-13
- Dec. 1974- Act 132 by D. Porter, PS #15410 Fnd Rec 4"x4" Sq Stk by F. Smith N75°W-13.20'-12" Elm
Rec L. 2, Pg. 45-50 N20°E-12.50'-6" Tw Brch S85°E-17.80'-14" Cedar
S85°E-49.35'-Conc Mon N70°E-34.10'-Conc Mon.
- Aug. 1982- Act 132 by F. King, PS #25852 - Fnd 3"x3" Stk - 49.2' West of Conc Mon @ Cor K-1 Rec L.3, Pg 170
No Recorded Act 74 Found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 - CORNER COMMON TO SECTIONS 35 & 36

- Found Remains of 4"x4" Post - Set 1/2" Iron
- N.70°E. - 34.50' (R-34.10') - Found Conc. Mon.
- S.85°E. - 49.35' - Found Rec Conc. Mon. @ Corner K-1, T29N-R1E
- S.85°E. - 17.6' (R-17.80') - Remains of Cedar Stump

APPROVED BY
PEER GROUP

JUN 02 95

[Signature]

This corner approved by Peer Review Committee on June 2, 1995, as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 - CORNER COMMON TO SECTIONS 35 & 36

- Set Conc. Mon. & County Re-Mon Cap @ Post Remains position
- N.20°E. - 12.50'- Set Tag in 6" Twin Birch
- N.70°E. - 34.50' - Conc. Mon.
- East - 17.80' - Set Tag 14" Stump
- N.75°W. - 13.20' - Set Tag in 12" Elm
- Corner K-1 is 49.35' East of Corner K-13
- Set Treated 2"x4" Stake alongside Corner K-13



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date 10-30-95