

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 2 E
T 30 NR 2 E ✓

Montmorency COUNTY

DESCRIPTION OF CORNER 1/4 corner on south side Section 36, T30N, R2E

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" R. Oak - N28E - 37 links
5" R. Oak - N45W - 51½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Many stumps in area but can find none to conform reasonably for government BTs.

North 1/4 corner for Section 1, T29N, R2E is 11 links east.

Corner was placed and witnessed July 11, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 7/11/60
REGISTERED LAND SURVEYOR