

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 30 NR 2 E ✓
T 30 NR 3 E

Montmorency COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25-36-30-31

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" R. Oak	-	S19W	-	18½ links
8" R. Oak	-	N62W	-	36½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Set corner by proportionate measurement between town corner and 1/4 corner north. Unable to identify the single government BT. This point conforms very closely with a clearing edge north, and is very good for line and measurement over 1/4 and section corner west. Cannot explain fence corner about 1.95 ch east, which conforms with no pattern of survey. Could not justify large deflection in town line on basis of fence corner which may have been located government measure from 1/4 corner east.

Corner placed and witnessed July 11, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 8/1/60