

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 29 NR 2 E
T 30 NR 2 E
T 29 NR 3 E
T 30 NR 3 E

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4-6-31-36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

7" Spruce - S80E - 22½ links

7" Spruce - N1E - 34½ links

8" Spruce - S74W - 28 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile west, 1½ miles north, 1 mile east, and 1 mile south by Forestry Division survey crew while making a survey of this area. Could find no evidence of original BTs, although several indications of previous search for witnesses were found. This point checks acceptably with swamp edges east, west and south, and was considered the most equitable method of restoration.

Corner was placed and witnessed July 11, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 8/1/60