

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 30 <sup>N.</sup> R. 2 <sup>E.</sup>	B-13; G-10; H-13
2. PROPERTY CONTROLLING IN SECTION.....	T. .... <sup>N.</sup> <sup>S.</sup> R. .... <sup>E.</sup> <sup>W.</sup>	.....
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. .... <sup>N.</sup> <sup>S.</sup> R. .... <sup>E.</sup> <sup>W.</sup>	.....
4. LOT NO. ...., RECORDED PLAT .....		
5. PRIVATE CLAIMS .....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 19, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


- A. Description of original monument and accessories and/or subsequent restoration:
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- B-13 Set by proportionate measurement between section corners; unable to positively identify U.S. evidence.
  - G-10 Set corner by proportionate measurement, midpoint on line, between section corners. Falls in centerline of N-S road.
  - H-13 Set corner at record measurement west of previously restored N $\frac{1}{4}$  Sec. 3 T29-2E. Appears to be as located and used in many previous surveys in this area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13	G-10	H-13
Set DNR monument	Set DNR monument	Set DNR mon. & red-top post
24" B. Cherry N50 <sup>o</sup> W 63.4	8" Maple N65 <sup>o</sup> W 50.8	10" Maple N35 <sup>o</sup> E 62.9
8" Maple N28 <sup>o</sup> E 101.6	11" Maple S48 <sup>o</sup> W 64.3	4" R. Pine N30 <sup>o</sup> W 28.45
N $\frac{1}{4}$ Sec. 6 T29N-R2E East 6.6	Cedar post West 36'	N $\frac{1}{4}$ Sec. 3, T29N-R2E East 19.4

SIGNED BY *Kenneth J. Ostling* DATE 12-1

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_  
 BRILEY TOWNSHIP  
 MONTMORENCY COUNTY