

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 30 N. R. 2 E.	E-13; G-13; J-13
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 30, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- E-13 Found 4" concrete monument in place, probably as established by G. F. DeLaMater survey. NW corner Sec. 4, T. 29 N., R. 2 E., is 13.2' East.
- G-13 Found concrete monument in place as previously established by G. F. DeLaMater survey. In N-S county road. NW corner Sec. 3, T. 29 N., R. 2 E., is 19.1' East.
- J-13 Found 1/2" iron bar at corner, during 1960 DNR survey. One possible USBT stump in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13	G-13	J-13
Left 4" conc. mon. in place set cedar post	Left 4" conc. mon. in place	Set DNR mon. in place of iron bar
5" R. Pine N35°W 11.4	28" Oak West 11.4	4" J. Pine N05°W 31.0
20" Oak S72°W 33.0	11" R. Pine N50°W 23.4	4" J. Pine N42°W 20.4
4" Conc.Mon. N45°W 50.0	Conc. Mon. N45°W 50.2	N 1/4 Sec. 2, T. 29 N., R. 2 E. is 19.22 E
4" Conc.Mon. N45°E 50.0	Conc.Mon. N45°E 50.1	

SIGNED BY Kenneth J. Ostling DATE 7/15/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ MONTMORENCY COUNTY