

Montmorency County Re-monumentation

Libel 12 Page 51

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-1)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
MONTMORENCY CITY
DEEDS
REGISTER
DEC 28 9 05 AM '93
Register
A. PHILIPAN-NEILROY

Register of Deeds Stamp & File Number

I, Larry G. Beauregard in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-1) GLO Post set by Lewis Clason April 1840.
Wits: Beech 14" S 34° E 2½ links Hard Maple 18" S 46° W 25 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-1) Didn't find original post or wits.
Set 4" x 36" Conc. Mon. & 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor. on the Monumented 3rd. correction line by extending the Twp. line N. from Rec. Corners. This position agrees well with GLO distance, East to Twp. Cor. T31N, R1E & R2E.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-1) Twp. Cor. Comm. to Sec. 1 & 6, T30N, R1E & R2E
4" dia. x 36" Conc. Mon. & Re-Mon. cap #18654. Accepted as a careful and faithful establishment of the position of the Corner, approved by the Peer Group on November 5, 1993.
S 75° W 9" Maple 14.01' N 85° E 5" Maple 52.32'
N 15° W 3" Ironwood 22.27' S 55° E 5" Ironwood 16.20'
Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 12-27-93
Surveyor's Michigan License No. 18654