

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-3)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
MONTMORENCY CITY
REGISTER
DEC 28 9 05 AM '93

A. P. PARSONS-RECORDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-3) GLO Post set by Lewis Clason April 1840.
 Wits: Beech 12" N 31° W 60 links Lynn 7" S 72° W 36 links
 Frank N. Smith P.S. # 706 Co. Surveyors in 1941 established Cor. wits marked:
 (N 45° E 50' Conc. Mon.) (S 45° W 50' Conc. Mon.).
 Gordon E. Slattery P.E. #3694 MDOT Project Engineer in 1967 fnd. Conc. Mon. 5" below gravel road surface, wits marked: (N 55° E 42.89' 7" Maple) (S 55° E 36.75' 9" Maple) (N 85° W 35.49' Cor. Fe. Post) (S 45° W 49.95' Conc. Mon.) (N 45° E 49.95' Conc. Mon.).
 Donald E. Marlatt P.S. #18660 in 1989 fnd. Conc. Mon., wits marked: (N 75° E 11" Maple 27.5') (S 50° E 8" Maple 41.9') (N 50° E 6" Ironwood 57.5').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-3) Fnd. Conc. Mon. by Smith 6" below road surface & one Conc. Mon. wits. This Mon. was broken & in bad condition.
 (Re-placed Mon. with new 4" dia. x 36" Conc. Mon. & 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor. set 6" below road surface.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-3) Sec. Cor. Comm. to Sec's 1 & 12, T30N, R1E & Sec's 6 & 7, T30N, R2E
 4" dia. x 36" Mon. & Re-Mon. cap #18654, 6" below road surface. Accepted as the best available evidence of the position of the original corner, approved by the Peer Group on September 24, 1993.
 West 40' 1/2" bar & cap #18660 N 88° E 38.78' 6" Ironwood
 N 75° E 27.95' (M) 27.50' (R) 11" Maple S 50° E 41.90' 7" Maple

Signed by Larry G. Beauregard
 Surveyor's Michigan License No. 18654

Date 12-27-93