

Montmorency County Remonumentation

Liber 12 Page 54

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

08350

RECEIVED  
MONTMORENCY COUNTY  
REC'D  
DEC 28 9 05 AM '93

For corners in

Montmorency (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-4)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-4) GLO Post set by Lewis Clason April 1840.  
Beech 11" S 8° W 68 links Hd. Maple 12" N 80° W 22 links  
Gordon E. Slattery P.E. #3694 MDOT Project Engineer in 1967 set 1" Iron pin 10" above ground, wits marked: (S 05° W 7.12' 6" Beech) (S 89° W 41.08' 8" Maple).  
(S 66° W 40.93' 23" Beech).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-4) Fnd. 1" pin 10" above ground by Slattery P.S. #3694.  
(Placed 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor. on same.)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-4) 1/4 Cor. Comm. to Sec's 7 & 12, T30N, R1E & R2E  
1" Iron pin & Re-Mon. cap #18654. Accepted as the best available evidence of the re-establishment of the position of the original corner, approved by the Peer Group on September 24, 1993.  
S 05° W 7.10' 12" Maple (R) NBT S 89° W 12.85' 6" Maple  
S 45° W 5.55' 15" Maple S 66° W 41.10' Tw. 27" Beech  
(Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93

Surveyor's Michigan License No. 18654

Revised 2-2-94 L.B.