

Montmorency County Remonumentation

Liber 12 Page 55

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-5)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED
 MONTMORENCY CITY
 REGISTER OF DEEDS
 Dec 28 9 05 AM '93
A. PANGAN-KOILROY

Register of Deeds Stamp & File Number

I, Larry G. Beauregard in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-5) GLO Post set by Lewis Clason April 1840.
 Wits: Hard Maple 12" S 12° W 28 links Beech 6" N 56° W 19 links
 Gordon E. Slattery P.E. #3694 Project Engineer MDOT in 1967 set 1" Re-bar flush with bit surface.
 Wits marked: (S 45° W 58.98' 21" Maple) (S 30° W 91.82' 7" Maple) (S 78° W 75.79' 6" Ironwood).
 Donald E. Marlatt P.S. #18660 fnd. 1" Re-bar & wits by Slattery in 1978 & in 1985 marked wits: (S 30° W 91.82' 9" Maple East 33' 1/2" rod.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-5) Fnd. 1" Re-bar 2" below pavement 2'± West of M-32 C/L.
 (Re-placed 1" bar with 1/2" bar & 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Corner & set Mon. box.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-5) Sec. Cor. Comm. to Sec's 12 & 13, T30N, R1E & Sec's 7 & 18, T30N, R2E
 1/2" bar & Re-Mon. cap #18654 in Mon. box. Accepted as the best available evidence of the position of the original corner, approved by the Peer Group on September 24, 1993.
 East 33.0' 1/2" bar & cap #18660 N 65° W 85.12' 6" W. Pine
 S 70° W 110.9' P. Pole S 55° W 88.30' Tw. 9" Beech

Signed by Larry G. Beauregard Date 12-27-93
 Surveyor's Michigan License No. 18654