

Montmorency County Re-monumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
MONTMORENCY COUNTY
RECORDS
DEC 28 9 06 AM '93
A. PANSKY-RECORDS

For corners in:

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-9)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Larry G. Beauregard in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (A-9) GLO Post set by Lewis Clason April 1840.
Wits: Hard Maple 20" S 52° W 14 links Beech 12" N 81° W 15 links
G.A. Shadko (Dept. of Conservation Survey) in 1943 set 1" O.D. pipe & marked Wits: (N 13° W 19.2' 7" Wt. Ash) (N 87° E 16.3' 5" Lynn) (S 31° W 7.0' 3" Maple)
Robert L. Mitchell P.S. #6936 fnd. pipe & wits in 1956.
Ronald R. Bischer P.S. #22428 (Porters Survey) fnd. pipe in 1977 & remarked wits above.
Filed Act 74, L. 1, P. 198. Wits: (N 13° W 19.14' 14" Wt. Ash) (N 87° E 15.96' 12" Lynn) (S 31° W 6.77' 6" Maple).
Leo R. Smith P.S. #10706 (Scott Engineering Inc.) fnd. 1" pipe & wits in 1960).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9) Fnd. 1" pipe by Shadko & wits by Bischer.
Replaced 1" pipe with 4" x 36" Conc. Mon. 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (A-9) Sec. Cor. Comm. to Sec's 24 & 25, T30N, R1E & Sec's 19 & 30 T30N, R2E
4" x 36" Conc. Mon. & Re-Mon. cap #18654, accepted as the best available evidence of the original corner, approved by the Peer Group on September 24, 1993.
N 85° W 13.50' 3" Beech NBT N 13° W 19.14' 16" Lynn (R) NBT
N 87° E 16.30' 12" Lynn (R) NBT S 31° W 6.70' 11" Maple (R) NBT
(Placed 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93
Surveyor's Michigan License No. 18654