

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>(A-10)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 MONTMORENCY COUNTY
 REGISTER OF DEEDS
 DEC 21 9 06 AM '93
 A. VAN DER WERF

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry G. Beauregard in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (A-10) GLO marked Hard Maple 22" for 1/4 post by Lewis Clason April 1840.
 No other wits.
 G.A. Shadko (Dept. of Conservation Surveyor) in 1943 set 1" O.D. pipe (No wits).
 Leo R. Smith P.S. #10706 (Scott Engineering Inc.) in 1960 fnd. 1" pipe (No wits).
 Larry G. Beauregard P.S. #18654 (Scott Engineering Inc.) in 1974 & 1980 fnd. 1" pipe & wits marked: (N 31° W 9" Maple 8.30'(R) (N 14° W 7" Maple 28.12') (S 04° E 6" Maple 11.13').
 Ronald R. Bischer P.S. #22428 (Porters Survey) in 1977 fnd. 1" pipe & filed Act 74 Rec. L. 1, P. 198. Wits same as above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (A-10) Fnd. 1" pipe by Shadko & wits by Larry G. Beauregard.
 Re-placed pipe with 4" x 36" Conc. Mon. & 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (A-10) 1/4 Cor. Comm. to Sec's 25, & 30, T30N, R1E & T30N, R2E
 4" x 36" Conc. Mon. & Re-Mon. cap #18654, accepted as the best available evidence of the original corner, approved by the Peer Group on September 24, 1993.
 N 31° W 8.20' 10" Maple (R) NBT Ex. blaze N 14° W 28.12' 8" Maple (R) NBT Ex. blaze
 S 04° E 11.13' 8" Maple (R) NBT Ex. blaze S 45° W 15.80' 4" Beech (N) NBT
 (Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93
 Surveyor's Michigan License No. 18654