

Montmorency County Remonumentation

FEB 08 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
MONTMORENCY

	Located In:	Corner Code #
(County)		
BRILEY TWP.	T <u>30N</u> R <u>2E</u>	<u>F-1</u>
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-12-1999 09:26:54

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DONALD E MARLATT, in a field survey on JULY 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-1 N. 1/4 COR. OF SEC. 4
NO CORNER SET GLO SURVEY.
G.F. DELAMATER PS#693(1932) 1/2"X30"BAR IN COR. POINTED STONE NORTH 29.6', POINT, POINTED STONE S45°W 46.6'.
COUNTY RD COMM. NOTES(1941) CONC. MONUMENT. WIT. MON.S S45°W 50' & S45°E 50'.
MSHD-GORDON SLATTERY FEB. 1968. FD. CONC. MONUMENT. S60°E 54.59'24"MAPLE, S45°E 50' CONC. MON., S45°W 50' CONC. MON., S75°W 74.44' 23"MAPLE.
N.C.CALDWELL PS#12018.FD. DELAMATER 1/2"BAR. NORTH 40' 1/2"BAR, CONC. MON. S45°W 50' 1973
L. BEAUREGARD PS#18654 7-14-97. FD. 1/2"BAR & CAP. NORTH 25.38' 4"MAPLE, N45°W 68.73' P.POLE, S50°W 42.83' 25"MAPLE 7"MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 N. 1/4 CORNER OF SEC. 4
FD. CONC. MON.
S51°W 24"MAPLE 42.85 R. S83°W 28"MAPLE 74.44' R.
S24°W 8"MAPLE 64.14' R. S52°W "X" ON STONE 46.6' R.
N 4°E 5"MAPLE 25.35' R. S60°E 54.6' 29"MAPLE R.
N44°W p.pole 68.75' R.
S49°W CONC. MON. 50'R.
NORTH 29.6' POINTED STONE R.

APPROVED BY
PEER GROUP

JUL 20 99

J.A.B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 NORTH 1/4 COR. SEC. 4
FD. CONC. MONUMENT & PLACED REMON. CAP ON SAME.
S82°W 26"MAPLE 74.3'
S50°W 26"MAPLE 42.87'
S52°E 26"MAPLE 54.45'
N43°W p.pole 68.70'
WITNESSES MARKED WITH 40PENNY SPIKES & PS TAG#18660.
APPROVED BY PEER GROUP JULY 20, 1999 AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.



Signed by Donald E Marlatt
Surveyor's Michigan License No. 18660

Date 11-8-99