

FEB 08 2000

Montmorency County Remonumentation

Liber 00012 Page 0379

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)	Located in: BRILEY	Corner Code #
1. Public Land Survey	T 30N R 2E	H-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-24-1999 15:51:12

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, FREDERICK J. KING, in a field survey on JULY 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-9 - 1/4 CORNER COMMON TO SECTIONS 22 & 27

- June 1840 - Lewis Clason, D.S. - Set Orig Post - S47°W-291ks (19.14')10" Elm * N37°E-36 lks (23.76') 9" J. Pine
- May 1974 - Act 132 by L.G. Beauregard, PS#18654 - Shows Cor Used - No Wit - Rec. L.1, Pg. 536 - Testimony from L.G. Beauregard, states that Barn Spk, fnd to be on line and at equal distance between G-9 & I-9 has been used and accepted by both himself & D.E. Marlatt, P.S.#18660 for previous surveys using Corner H-9
- July 1999 - Advised by D.E. Marlatt, PS#18660 he placed 1/2" Iron & ID Cap at Spk Position, on line & Equal Dist between Corners G-9 and I-9 - No Wit. - Not Recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 - 1/4 CORNER COMMON TO SECTIONS 22 & 27

Fnd 1/2" Iron and ID Cap #18660 as set by D.E. Marlatt



This Corner was Approved by Montmorency County Peer Review on July 20, 1999, as a careful and faithful establishment of the position of the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 - 1/4 CORNER COMMON TO SECTIONS 22 & 27

- Set Conc. Mon and Re-Mon Cap at Fnd I&C Position
- N 45°E - 42.11' - Set S&T on SE side of 24" R. Pine
- S 20°E - 53.54' - Set S&T on W side of 15" J. Pine
- S 25°W - 36.94' - Set S&T on W side of P. Pole #AA3-155
- N 50°W - 67.05' - Set S&T on NE side of 27" W. Oak
- Cor Is 2' N of C.L. E-W Gravel Rd. (Co. Rd. 489) and In line of C.L. 2-Track to N. and 10' W of Old Fnc to N.

APPROVED BY
PEER GROUP

Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date October 18, 1999 JUL 20 99

J.H.B.