

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY
(County)

Located in:

Corner Code #

BRILEY TWP.
1. Public Land Survey

T	30N	R	2E	I - 1
T		R		
T		R		
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-12-1999 09:26:38

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DONALD E MARLATT, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I - 1 NORTH CORNER COMMON TO SECTIONS 2 & 3.
GLO CORNER SET LEWIS CLASON IN APRIL 1840.
TAM 6" S34°E 35 L., TAM. 8" S19°W 10 L.
D.E.MARLATT PS #18660 ACT 132 DATED 7-7-82. FOUND 1/2" ROD. S40°W 47.28' 8" TAMRACK, S30°E 44.4' 8" CEDAR. (NOT RECORDED)
D.E.MARLATT ACT 132 DATED 10-11-94 LIBER 10004, PAGE 243. FOUND 1/2" ROD. N15°E 9" TAMRACK 42.92', S40°W 47.2' 9" TAMRACK, S30°E 44.4' 9" CEDAR, SOUTH 33' 1/2" ROD & CAP #18660.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 1 NORTH COR. COMMON TO SEC.S 2 & 3
FOUND 1/2" ROD
N15°E 9" TAMRACK 42.92' R.
S40°W 9" TAMRACK 47.2' R.
S30°E 44.4' 9" CEDAR R.
SOUTH 33' 1/2" ROD & CAP #18660

APPROVED BY
PEER GROUP

JUL 20 99

J. L. B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 1 NORTH CORNER COMMON TO SEC.S 2 & 3.
PLACED REMON. CAP ON 1/2" ROD DROVE IN LOG BURIED IN ROAD.
N26°E 9" TAMRACK 42.84'
S30°E 10" CEDAR 44.56'
S40°W 9" TAMRACK 47.22'
S10°W 10" TAMRACK 33.13'



WITNESSES MARKED WITH 40 PENNY SPIKES & PS TAGS #18660.
APPROVED BY PEER GROUP JULY 20, 1999 as BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Donald E Marlatt
Surveyor's Michigan License No. 18660

Date 11-8-99