

FEB 08 2000

Montmorency County Remonumentation

Liber 00012 Page 0370

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY  
(County)

Located In:

Corner Code #

BRILEY TWP.  
1. Public Land Survey

T30N R 2E I - 3

T R

T R

T R

2. Property Controlling  
in Section

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

S T R

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-12-1999 09:26:28

TERESA WALKER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DONALD E MARLATT, in a field survey on JULY, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3								●				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I - 3 CORNER COMMON TO SEC.S 2-3-10 & 11

GLO CORNER SET BY LEWIS CLASON APRIL 1840. W.PINE 7" N52°E 16 L, Y.PINE 6" S27°W 19 L.

FRANK SMITH PS#754 NOTES-BALSAM 6" S76°W 16.7', BALSAM 10" N13°30'E 36.1', N.PINE 14" S14°W 22.1'

COUNTY RD. COMM. NOTES(1941)CONC. MON. COR. N45°W 50' CONC. MON., S45°E 50' CONC. MON.

D.E. PORTER PS#15410.ACT 132 3-22-76, L. 2, P. 148. FD. CONC. MON. N45°W 50' CONC. MON., N15°E 36.28' 10"BIRCH, N88°E 26.69' 26"MAPLE.

RON BISCHER PS#22428 ACT 74, 4-10-76, L. 1, P. 160. FD. CONC. MON. N45°W 50' CONC. MON., S45°E 50' CONC. MON., N15°E 36.28' 10"BIRCH, N88°E 26.69' 26"MAPLE.

D.E.PORTER ACT 132 DATED 6-27-77, L. 2, P. 365. FD. CONC. MON.(WIT. SAME AS ABOVE).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 3 CORNER COMMON TO SEC.S 2-3-10 & 11.

FD. CONC. MONUMENT

N45°W 50' CONC. MONUMENT R.

S45°E 50' CONC. MONUMENT R.

N88°E 26.69' 26"MAPLE R.

APPROVED BY  
PEER GROUP

JUL 20 99

*H.H.B.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 3 CORNER COMMON TO SEC.S 2-3-10 & 11.

PLACED REMON. CAP ON EXISTING CONC. MONUMENT.

S87°E 29"MAPLE 26.1'

S41°E 50' WIT. CONC. MONUMENT

N15°E 12"BIRCH 35.91'

N41°W 50' WIT. CONC. MONUMENT

N28°W 8"SPRUCE 28.32'

S16°E 8"MAPLE 14.66'

WITNESSES MARKED WITH 40 PENNY SPIKES AND PS TAG #18660.

APPROVED BY PEER GROUP JULY 20, 1999 as THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Donald E Marlatt  
Surveyor's Michigan License No. 18660

Date 11-8-99

