

FEB 08 2000

Montmorency County Remonumentation

Liber 00012 Page 0386

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY
(County)

Located in: BRILEY Corner Code #

- 1. Public Land Survey T 30N R 2E 1-7
T R
T R
T R
- 2. Property Controlling In Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-24-1999 16:06:01

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, FREDERICK J. KING, in a field survey on JULY 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1-7 - CORNER COMMON TO SECTIONS 14, 15, 22 & 23

- June 1840 - Lewis Clason, D.S. - Set Orig. Post - N27°W-29 lks(19.14') 14" Cedar * S53°E-13 lks (8.58') 9" Cedar
- July 1934 - F. Smith, PS# 754 - 4"x4" Cedar Stk (1)S84 W-16.7'-4" Spruce (2) S7 E-19.7'-5" Tam (3)N85 E-29.0'-5" Tam Field Book (MCRC - Rec)
- July 1974 - D.E. Porter, PS#15410 -4" Sq Stake (1)S84 W-16.7'-4" Spruce (3)N85 E-29.0'-5" Tam -(Rec. L.1, Pg. 568-Act 132)
- Oct. 1974 - L.G. Beauregard, PS#18654 - Act 132 - No COr Desc - No Wit -(Rec. L.2, Pgs 546-553)
- May 1976 - D.E. Porter, PS#15410 - 4" Sq Stk - Same Wit as L.1, Pg. 568 - (Rec. L.2, Pg. 174-176-Act 132)
- June 1978 - D.E. Marlatt, PS#18660 - Fnd 1/2" Rod & Sq Stk (1)S84 W-19.7'-9" Spruce (3)N85 E-29' -5" Tam. (Rec.L.2, Pg.515)
- UNKNOWN - Porters Survey wit Records - 4"x4" Cedar Stk - Same Wit as F. Smith Field Book (MCRC - Rec)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1-7 - CORNER COMMON TO SECTIONS 14, 15 22 & 23
- Fnd 1/2" Iron Alongside rotted off 4"x4" wood stk.
- Iron Is in Old E-W Fence
- Fnd Witnesses #1 & #3

APPROVED BY
PEER GROUP

JUL 20 99

F.J.B.

This Corner was Approved by Montmorency County Peer Review on July 20, 1999 as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7 - CORNER COMMON TO SECTIONS 14, 15, 22 & 23

- Placd Conc. Mon and Re-Mon Cap at Fnd 1/2" Iron Position
- N 40°E - 3.75' - Set S&T on SE side of 7" Cedar
- N 85°E - 29' - Rec. Tam (Now Dead)
- S 35°E - 5.27' - Set S&T on SW side of 7" Cedar
- S 10°E - (R-S07°E) - 19.5' (R-19.7') Rec. Tam (Now Dead)
- S 80°W - (R-S84 W) - 19.83' (R-16.7' & 19.7') - Set S&T on S side of 10" Spruce.
- N 55 W - 23.91' - Set S&T on SW side of 5" Cedar
- Corner Is In Old E-W Fence.



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date October 18, 1999