

FEB 08 2000

Montmorency County Remonumentation

Liber 00012 Page 0388

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MONTMORENCY</u> (County)	Located In: BRILEY	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>J-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-24-1999 16:06:18

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, FREDERICK J. KING, in a field survey on JULY 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5									●			
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-5 - 1/4 CORNER COMMON TO SECTIONS 11 & 14

- June 1840 - Lewis Clason, D.S. - Set Orig. Post - Marked 8" Tam for 1/4 Post - No Witnesses Marked
- 1941 - F. Smith, PS# 754 - Field Notes - Pipe Set In Conc (1)N45°E-50.0'-4" Conc Mon (2)S45°W-50.0'-4" Con Mon.
- 1959 - L.R. Smith, PS#10706 - No Cor Desc. - No Wit - On File @ Reg of Deeds
- July 1977 - D.E. Marlatt, PS#18660 - Act 132 - Fnd Mon - Wit #1 & #2 Rec. L.2, Pg. 352
- UNKNOWN - Porters Survey Witness Records - Conc Mon - Wit #1 - Wit #2 (3)S68°E-31.5'-4" Pine (4)N75°E-23.4'-3" Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 - 1/4 CORNER COMMON TO SECTIONS 11 & 14

Fnd Conc. Mon & Witnesses #1, #2, & #4

APPROVED BY
PEER GROUP

JUL 20 99

L.G.B.

This Corner was Approved by Montmorency County Peer Review on July 20, 1999, as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 - 1/4 CORNER COMMON TO SECTIONS 11 & 14

- Placed Re-Mon Cap on Fnd Conc. Mon.
- N 45°E - 49.95' (R-50.0') - Fnd Conc. Mon
- N 55°E - 25.22' - Set S&T on N side of 24" R. Pine
- S 65°E - (R-S68 E) - 31.97' (R-31.5') Fnd Tag #41922 on N side of 24" R. Pine
- S 45°W - Approx. 50' - Fnd Conc Mon Laying on Side
- S 55°W - 5.68' - Fnd Tag #41922 on NW side 3" W. Pine
- N 40°W - 42.07' - Fnd Tag #41922 on NE side of P. Pole
- Corner is in Line with Gravel Rd to N on S side of Split Rail Fence and between Drives SE and SW.



Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date October 18, 1999