

SURVEY & REMONUMENTATION

Montmorency County Remonumentation

Liber **00012** Page **0132**

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Montmorency
(County)

Located in:
Briley Township

Corner Code #

1. Public Land Survey

T 30 N R 2 E
T 30 N R 2 E

J-13 ✓
K-13

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____

**APPROVED BY
PEER GROUP**

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

MAY 1 3 94

SLB

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-10-1994 14:13:14

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Don Marlatt, in a field survey on November 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-13) S. $\frac{1}{4}$ Cor. Sec. 35, T 30 N, R 2 E
Post set by Lewis Clawson 1-10-1840.
24" W. Pine N 50° E 30 links
6" Spr. Pine N 64° W 11 links
DNR Survey in Sept. 1977.
Ken Ostling - Recorded Act 74, Sept. 1977.

(K-13) South Cor. common to Secs. 35 & 36, T 30 N, R 2 E
Post set by Lewis Clawson 1-10-1840.
24" J. Pine N 62° E 61 links
26" J. Pine N 32° W 62 links
DNR Survey in Sept. 1977.
Ken Ostling - Recorded Act 74, L. 1, P. 211.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-13) S. $\frac{1}{4}$ Cor. Sec. 35, T 30 N, R 2 E
Found DNR Monument.
4" J. Pine N 5° W 31'
4" J. Pine N 42° W 20.4'
N. $\frac{1}{4}$ Cor. Sec. 2, 29/2, 19.22' East
No evidence of original corner.

(K-13) South Cor. common to Secs. 35 & 36, T 30 N, R 2 E
Found DNR Monument.
12" Oak N 37° E 15.6'
2" Spruce N 35° W 35.0'
N.E. Cor. Sec. 2, 29/2, 14.57' East
No evidence of original corner.

Accepted as a careful and faithful perpetuation of the original corner.

Accepted as the best available evidence of the reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-13) S. $\frac{1}{4}$ Cor. Sec. 35, T 30 N, R 2 E
DNR Monument.
8" J. Pine West 17.3'
11" J. Pine S 85° W 4.04'
12" J. Pine South 16.78'
12" J. Pine N 42° W 20.4'
12" Poplar N 15° E 13.93'
Pine stump N 4° E 21.2'
N. $\frac{1}{4}$ Cor. Sec. 2, 29/2, 9.4' East

(K-13) South Cor. common to Secs. 35 & 36, T 30 N, R 2 E
DNR Monument.
Tw. 11" Maple N 85° W 64.55'
13" Oak N 52° W 55.57'
15" Oak S 35° E 17.52'
14" Oak N 40° E 16.24'



Witnesses marked with a 30 penny spike & I.D. tag #18660/

Signed by Donald E. Marlatt

Date 11-9-1994

Surveyor's Michigan License No. 18660