

**SURVEY &
REMONUMENTATION**

NOV 23 1999

Liber 00012 Page 0354



**SECTION
MONTMORENCY COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corner(s) _____

<u>Montmorency</u> (County)	Located In: <u>Briley</u> (Township)	Corner Code # <u>K-11</u>
1. Public Land Survey	T <u>30N</u> R <u>2E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

08-10-1999 14:45:38

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File
Number

I, Larry G. Beauregard, in a field survey on April, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-11- Sec. Corner common with 25, 26, 35 & 36, T30N, R2E

1840 - Lewis Clason, D.S. Marked. (Y. Pine 10" for Sec. Post)

1972-1974 - Delmer E. Porter, RLS #15410. Fnd. 3' x 3' sq. Cedar Stk. & one Wit. (14" Oak N75W 84.74'). Placed 1/2" bar w/RLS cap. Filed LCRC, Rec. L. 1, P. 59. Wit's mkd. (14" Oak N75W 84.74') (R) (12" Blk Cherry in clump S50E 100.46') (10" Oak Due S. 117.28'). Filed Act #132 (1974), Rec. L. 1, Pgs. 562 - 557. Two of the same Wit's as above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April, 1999 - Fnd. 3' x 3' sq. Cedar Stk., 1/2" bar w/cap & Wit's by Porter. Corner of old fence is 15±N. with remains of old fence running N. & E. mostly down. Replaced 3' x 3' sq. Cedar Stk. & 1/2" bar w/cap with a 3 1/4" Aluminum Re-mon. cap on a 4" dia. X 36" concrete monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-11 Sec. Cor. common with 25, 26, 35, & 36, T30N, R2E

3 1/4" Aluminum Re-mon. cap on 4" dia. X 36" concrete monument.

Accepted as the best available evidence of the re-establishment of the original corner.

Approved by the Peer Group on July 20, 1999.

**APPROVED BY
PEER GROUP**

JUL 20 99

N50°W 84.74' (R & M) 24" W. Oak (R) (Ex. Tag #15420) (Placed 60d Spike & P.S. Tag 18654)
S36°E 100.46' (" & ") 11" Cherry - dead (R) (" " " ") (" " " ")
S18°W 117.28' (" & ") 16" Oak (" " " ") (" " " ")
S40°E 6.62' 8" Norway (R) (Ex. Nail & Tag #26466)
S50°W 4.63' 11" Norway (R) (" " " ")
S76°W 17.45' 10" Norway (R) (" " " ")

Signed by Larry G. Beauregard
Surveyor's Michigan License No. 18654

Date, August 5, 1999

