

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

For corners in

MONTMORENCY (County)

Located In:

Corner Code #

STATE OF MICHIGAN MONTMORENCY COUNTY Recorded & Filed

11-12-1999 09:25:43

TERESA WALKER REGISTER OF DEEDS

Register of Deeds Stamp & File Number

BRILEY TWP. 1. Public Land Survey

T 30N R 2E L - 1

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. Recorded Plat 5. Private Claims

I, DONALD E. MARLATT, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column M and row 1.

A. Description of original monument and accessories and/or subsequent restoration:

L - 1 NORTH 1/4 CORNER OF SEC. 1 NO CORNER SET ON GLO SURVEY

D.E. PORTER PS#15410 ACT 132 DATED 8-10-73. L. J, P.386. FD. 1 1/2"PIPE. 7"OAK N 5°W 20.45' 16"OAK N80°W 47.58', 8"OAK S80°E 14.90'.

D.E. PORTER ACT 132 DATE 2-27-75.L. 2, P. 70. FOUND 1 1/2"PIPE. N 5°W 7"OAK 20.45', N80°W 47.58' 16"OAK, S80°E 14.9' 8"OAK

D.E. PORTER ACT 74 DATED 3-6-75 L. 1, P.141. FOUND 1 1/2"PIPE. N 5°W 7"OAK 20.45', S80°E 14.90' 8"OAK, N80°W 47.58' 16"OAK.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 1 NORTH 1/4 CORNER OF SEC. 1.

FOUND 1 1/2"PIPE

N80°W 47.58' 20"OAK R.

S80°E 14.90' 12"OAK R.

N 5°W 20.45' 11"OAK R.

APPROVED BY PEER GROUP

JUL 20 99

F.A.B.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 1 NORTH 1/4 CORNER OF SEC. 1

SET CONC. MONUMENT AND REMON. CAP.

N56°W 47.4' 20"OAK

N10°E 11"OAK 20.07'

S63°E 12"OAK 15.0'

S82°W 13"OAK 65.15'

WITNESSES MARKED WITH 40 PENNY SPIKES & PS TAGS# 18660.

APPROVED BY PEER GROUP JULY 20, 1999 AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE POSITION OF THE CORNER.

Signed by Donald E Marlatt

Date 11-8-99

Surveyor's Michigan License No. 18660

