

FEB 08 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)	Located In:	Corner Code #
BRILEY TWP. 1. Public Land Survey	T 30N R 2E	L - 3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-12-1999 09:25:35

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	F
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		11		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DONALD E MARLATT, in a field survey on JULY 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L - 3 1/4 COR. COMMON TO SEC.S 1 & 12
GLO COR. SET-LEWIS CLASON IN APRIL 1840. Y.PINE 6" N44°E 18 L., Y.PINE 6" S56°W 20 L.
F. SMITH PS#754 NOTES-A.B.VALENTINE REESTABLISHED-DUG HOLE 2'DEEP-DROVE OAK STK.IN BOTTOM,
SET LIMESTONE 14"X8"X 6" IN BOTTOM, MARKED 1/4 WITH BROKEN BIRCH IN BOTTOM WITH BROKEN BIRCH
AROUND OUTSIDE OF STONE. OAK 8" N 2°E 14.3', OAK 8" S44°E 27.1'.
COUNTY RD. COMM. NOTES(1941). CONC. MON.COR. N45°W 50' CONC. MON., S45°E 50' CONC. MON.
D.E.PORTER PS#15410 ACT 132 DATED MAY 15, 1974. L. 1, P. 531. FD. CONC. MON. 16 & 12" TW. OAK
14.56' N23°E, CONC. MON. S45°E 50.18', 14"OAK S34°W 49.68'. ALSO RECORDED IN L., P. 343.
D.E. PORTER ACT 132 DATED 8-10-73 . L. 1, P. 386. (OUT OF PLACE) WIT. & DESCRIPTION DON'T FIT.
D.E. MARLATT PS#18660 ACT 132 DATED 10-10-75. L. 2, P.129. FD. CONC. MON. NOT WITNESSES.
D.E. MARLATT ACT 132 DATED 11-3-80. FD. MON. TW 14 & 18"OAK N23°E 14.56', CONC. MON. S45°E
50.18', 14"OAK S34°W 49.68'.NOT RECORDED.
D.E.MARLATT ACT 132 DATED 2-23-87. FD. CONC, MON. N23°E TW 14"OAK 14.56', S45°E MONUMENT
50.18', S34°W 14"OAK 49.68'. NOT RECORDED.

B. Description of cor. evidence found and/or method applied in restoring or reestablishing corner
L - 3 1/4 COR. COMMON TO SEC.S 1 & 12.
FOUND CONC. MONUMENT
N23°E 21 & 17"TW.OAK 14.56' R.
S45°E CONC. MONUMENT 50.18' R.

APPROVED BY
PEER GROUP

JUL 20 99
L.H.B.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
L-3 1/4 COR COMMON TO SEC.S 1 & 12.
PLACED REMON CAP ON EXISTING CONC. MONUMENT.
N24°E 17" & 21"TW OAK 13.92'
EAST 15"OAK 31.55'
S41°E CONC. MONUMENT 50'
S 3°E 16"OAK 46.10'

WITNESSES MARKED WITH 40PENNY SPIKES AND PS TAGS #18660.
APPROVED BY PEER GROUP JULY 20, 1999 AS THE BEST AVAILABLE EVIDENCE OF THE REESTABLISHMENT OF THE ORIGINAL CORNER.

Signed by Donald E Marlatt
Surveyor's Michigan License No. 18660

Date 11-8-99