

FEB 08 2000

Montmorency County Remonumentation

Liber 00012 Page 0396

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MONTMORENCY (County)	Located in: BRILEY	Corner Code #
1. Public Land Survey	T 30N R 2E	L-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-24-1999 16:07:13

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, FREDERICK J. KING, in a field survey on July 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

L-7 - 1/4 CORNER COMMON TO SECTIONS 13 & 24

June 1840 - Lewis Clason, D.S. - Set Orig Post - S47*W-85 lks (56.10')-6" Spruce 13

N32*E-91 lks(60.06')-6" Spruce

1941 - F.N. Smith, PS#754- 2 1/2" Conc Mon (1) N45*W-50.0'-Conc Mon (2) S45*E-50.0'-Conc Mon (3) S85*W-33.1'-P.Pole

(4)S42*E-42.5'-Fnc Post (5) N70*E-58.2'-9" J.Pine (6) S24*W-68.15'-T.Pole (7) N43*E-70.0'-4" J.Pine (MCRC Re

Oct. 1949 - F.N. Smith, PS#754 - Cert of Sur - Conc Mon Burried In Rd - No Wit (Not Rec)

Jan. 1950 - F.N. Smith, PS#754 - Cert of Sur - Conc Mon Burried In Rd - No Wit (Not Rec)

May 1952 - F.N. Smith, PS#754 - Cert of Sur - Conc Mon Burried In Rd - No Wit (Not Rec)

Jan. 1956 - M-33 Re-Location Project #60-10 by L. Schmalzried (Sur Chief) Fnd 1/2" Iron Pin (8) N28*E-73.0'-7" Pine

(9) N52*E-60.51'-7" Oak (10) N70*E-78.41'- 9" Pine

Jan. 1958 - G.G. Slattery, PE#3694 - Cert of Sur - No Cor Desc - No Wit (On File @ Reg of Deeds)

HISTORY CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

L-7 - 1/4 CORNER COMMON TO SECTIONS 13 & 24

FOUND 5/8" IRON IN MONUMENT BOX

Found Witnesses #5, #7, & #9

APPROVED BY
PEER GROUP

JUL 20 1999

L.G.B.

This Corner was Approved by Montmorency County Peer Review on July 20, 1999, as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 - 1/4 CORNER COMMON TO SECTIONS 13 & 24

Placgd 1/2" Iron & Re-Mon Cap over Fnd 5/8" Iron In Mon Box

N 50°E - (R-N52 E) - 60.61' (R-60.57') - Set S&T above Fnd Spk on SW side of 12" Oak

S 45°E - 50.90' - (R-50.00') - Fnd Conc. Mon

S 85°W - 64.27' - Set S&T on N side of P. Pole #AA3-88-21

WEST - 32.97' - (R-33.00') - Fnd Conc. Mon.

Corner Is In C.L. Rd to E and 1' E of C.L. N-S B.T. Rd. (Co. Rd. #487)



Signed by Frederick J. King

Date October 18, 1999

Surveyor's Michigan License No. 25852

A. Description of original monument and accessories and/or subsequent restoration (CONTINUED FROM FRONT)

- Nov. 1973 - D.E. Marlatt, PS#18660 - Act 132 - No Cor Desc - No Wit (Rec. L. 1, Pg. 462)
Mar. 1976 - D.E. Marlatt, PS#18660 - Act 132 - Exist Monument Box - No Wit (Rec. L. 2, Pg. 149)
July 1977 - D.E. Marlatt, PS#18660 - Act 132 - Existing Monument Box * (8) WEST-33.0'-Conc Monument
(Rec L. 2, Pg. 348)
Oct. 1980 - D.E. Porter, PS#15410 - Act 132 - 5/8" Bar In Monument Box * (7)N44°E-70.07'-6" J.Pine * (5)N66°E-58.22'-10"
(9)S81°W-65.80'-P.Pole (Rec. L. 3, Pg. 68)
Oct. 1980 - R.R. Bischer, PS#22428 - Act 74 - 5/8" Bar In Monument Box * Same Witnesses As L. 3, Pg. 68
(Rec. L. 1, Pg. 283)

SURVEY &
REMONUMENTATION

FEB 08 2000

SECTION