

NOV 23 1999



MONTMORENCY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Order's of
Montmorency
(County)

Located In:
Briley
(Township)

Corner Code #

- 1. Public Land Survey T 30N R 2E L-9
2. Property Controlling In Section S T R
3. Miscellaneous Property In Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

08-10-1999 14:46:50

TERESA WALKER
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Larry G. Beauregard, in a field survey on April, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column J and row 9.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9 - 1/4 Corner to 24 & 25, T30N, R2E

1840 - Lewis Clason, D.S. Set Cr. Sec. Post. Wit's mkd. (Y. Pine 26° S34E 23 lks) (DO 24° N21W 15 lks).

1941 - Frank N. Smith, RLS #754. Set 2 1/2" Conc. Mon. for Cor. Wit's set. (N45W 50.0' 4" conc. mon.) (S45E 50.0' 4" conc. mon.)

No Date - Montmorency Co. Road Commission Records. Fnd. Cor. & mkd. Wit's. (Blk. Oak 16° N64°-30'E 47.7') (Tel. Pole S50°-45W 33.5') (Y. Pine 18° N62°W 55.2') (Poplar 6° S45°-15E 47.15')

1955-1956 - MDOT Survey of M-33 Relocation from Oscoda Co. Line Northerly to Atlanta. Survey Chief, L. Schmalzried. Fnd. 1" Iron Pin. Wit's. Mkd. (Pine 15° N20W 64.56) (Pine 15° S85W 69.95) (Pine 10° S15E 97.00)

1972-1974 - Delmer E. Porter, RLS #15410. Fnd. or set 1/2" w/RLS cap & wit's by Smith. Filed LCRC, Rec. L. 1, P. 59. Wit's mkd. (4" Conc. Mon. N45W 50.0') (4" Conc. Mon. S45E 50') (14" Y. Pine S85W 69.93') (14" Y. Pine N15W 64.40'). Filed Act #132's, Rec. L. 1, Pgs. 288 - 291 & L. 1, Pgs. 292 & 293. Same Wit's as above.

1975 - Donald E. Mariatt, RLS #18660. Fnd. Ex. Mon. Filed Act #132, Rec. L. 2, P. 125. No Wit's mkd.

1999 - Larry G. Beauregard, RLS #18654. Fnd. 1" bar in Mon. Box West edge of Rd. South & in the C/L Co. Rd. N. & E. Filed Act #132, Rec. 10005, Pgs. 0034 & 0035. Wit's Mkd. (S40°E 49.90' 10" W. Pine) (S25°W 57.55' 12" N. Pine) (N35°W 52.85' 1/2" bar w/RLS cap #15410) (West 33.05' 1/2" bar w/RLS cap #15410).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April, 1999 - Fnd. Conc. Mon. in Mon. Box & Wit's mentioned above, plus Conc. Mon's. by Smith (N45°W & S45°E 50.0'). Placed a 3 1/4" Aluminum Re-mon. cap on Mon. in Mon. Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 - 1/4 Corner to Sec. 24 & 25, T30N, R2E

3 1/4" Aluminum Re-mon. cap on concrete monument in Mon. Box.

Accepted as the best available evidence of the re-establishment of the original corner.

Approved by the Peer Group on July 20, 1999.

- N45°W 50.00' (R & M) (Existing 4" dia. Conc. Monument) (R)
S45°E 50.00' (" ") (" " " ") (R)
S38°E 57.55' 12" Norway (Placed 60d spike & P.S. Tag #18654)
S54°E 49.90' 9" W. Pine (" " " ")

APPROVED BY
PEER GROUP

JUL 20 99

L.G.B.

Signed by Larry G. Beauregard

Date, August 5, 1999

Surveyor's Michigan License No. 18654