

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency (County)	Located In	Corner Code #	
1. Public Land Survey	T 30N R 2E	E-11	
	T	R	
2. Property Controlling in Section	S T	R	
	S T	R	
3. Miscellaneous Property in Section	S T	R	
	S T	R	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Carl T. Kiiskila, in a field survey on July 29, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

E-11 Liber 12, Page 409, Larry G. Beauregard P.S. #18654 found a 2 1/2" concrete monument at the corner. He placed a 3 1/4" aluminum remonumentation cap on the found monument.

- Wit: N45°E 50.00' Fd. 4" dia. concrete monument  
 N45°W 50.00' Fd. 4" dia. concrete monument  
 S69°W 85.65' 36" Oak  
 S60°E 74.68' P. Pole  
 S60°E 74.54' P. Pole

Liber 1, Page 602, I Carl Kiiskila found a 1/2" iron pipe that we dug up and assumed to be the corner common to section 28,29,32, and 33. Please disregard this 1/2" pipe as being the corner. At the time I dug up this corner I was unaware that there was a concrete monument with a re-monumentation cap approved for this corner.

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

E-11 Found a concrete monument with a Montmorency County re-monumentation cap fitting Larry G. Beauregard's witnesses from above.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-11 Concrete monument with a Montmorency County re-monumentation cap.

- Wit: Concrete Monument N49°E 50.00'  
 Concrete Monument S49°W 49.16'  
 36" Oak N67°W 85.60'  
 P. Pole w/ P.S. tag #18654 S52°E 74.64'  
 P. Pole w/ P.S. tag #24600 S52°E 74.55'  
 1/2" pipe N85°W 0.80'



Signed by: Carl T. Kiiskila  
 Surveyor's Michigan License No.: 33981

Date: 8-5-02