

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Montmorency (County)	Located In	Corner Code #
1. Public Land Survey	T 30N R 2E	A-11
	T 30N R 2E	B-12
2. Property Controlling in Section	S T R	_____
	S T R	_____
3. Miscellaneous Property in Section	S T R	_____
	S T R	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on May 3, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-11 G.L.O. Lewis Clason D.S. 1839
Set post corner of sections 25 and 26
Wit: Cedar 9 S15°W 43 links
Cedar 10 N44°W 15 links

B-12 G.L.O. This corner position was not established during the original government survey.

Gregory a Shadko R.L.S. #1934 P.A.S. survey
March 1943 set conc. marker 4" X 60 with bronze plate

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A-11 Found D.N.R. public access site monument

B-12 Established the center of section 31 at the intersection of the North-South and East- West quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Found D.N.R. public access site mon.

Wit: *7" Cedar N82°E 34.10'
*10" Cedar S35°E 18.71'
*8" Cedar S70°W 14.42'
*8" Tamarack N42°W 33.65'

B-12 Set 5/8" X 32" rerod with P.S. cap #33981

Wit: 6" Maple S25°E 45.24'
4" Twin Maple S77°E 18.41'
6" Twin Maple N70°E 58.03'
10" Oak East 54.97'
Carsonite post North 1'±

* old witnesses by others

Signed by:

Carl T. Kiiskila

Date:

3-7-02

Surveyor's Michigan License No.:

33981

