

✓

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
FORESTRY DIVISION

**LAND CORNER RECORD**

T. 29 NR. 3 E ✓  
T 30 NR 3 E ✓

----- Montmorency ----- COUNTY

DESCRIPTION OF CORNER Closing Corner common to Sections 5 and 6  
on north boundary of T29N, R3E

DESCRIPTION OF CORNER MONUMENT. 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

9" Aspen-S49E	-	25½ links
10" Aspen	-	889W - 78 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored at record government measure from standard corner to Sections 31 and 32, T30N, R3E, by Forestry Division survey crew while making a survey in this area. Stumps in general area for possible government BTs, but they do not conform very well with government record. Unable to locate anything more conclusive.

Corner to Sections 31 and 32, T30N, R3E is 10 links west.

Corner was placed and witnessed July 11, 1960.

SURVEYORS SEAL

SIGNED *Kenneth Postling* DATE 8/1/60  
REGISTERED LAND SURVEYOR