

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

✓

LAND CORNER RECORD

T. 29 NR. 3 E  
T 30 NR 3 E

Montmorency COUNTY

DESCRIPTION OF CORNER Closing corner common to Sections 4 and 5  
on North boundary of T29N, R3E  
DESCRIPTION OF CORNER MONUMENT Wood post

WITNESSES TO CORNER

6" Basswood	-	S16W	-	9½ links
7" Basswood	-	S54E	-	18 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a survey in this area. Set corner at record measurement east of standard corner, which falls about 2' SW of a squared post previously set for closing corner. Short Cedar post sets in a hole which appears to be evidence of digging for government corner. Unable to identify OBTs, however, so set corner at latitude prescribed by standard corner and at record measurement east.

Corner to Sections 32 and 33, T30N, R3E is 15 links west.

Corner was placed and witnessed July 12, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 8/1/60 -