

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------|----------------|
| <u>Montmorency</u> (County) | Located In: | Corner Code ## |
| | AVFRY TWP. | H-13 |
| 1. Public Land Survey | T <u>30N</u> R <u>3E</u> | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
 MONTMORENCY COUNTY
 Recorded & Filed

11-21-1995 13:22:59

A. PANGAN-MCELROY
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Donald E. Marlatt, in a field survey on 4-24-1995, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-13) S. ¼ corner of Section 34, T 30 N, R 3 E.
 Post set by Lewis Clason in 1840. N 9* E 10" Fir 1.09 links. N 5½* W 6" Cedar 1.15 link
 R.S. Scott Engineering Survey on 6-13-1967. FOUND PIPE-NO WIT.
 Norman Caldwell Survey on 1-15-1968. FOUND POST WITH PIPE-SET ½" BAR & CAP (WIT. SOUTH 2.1'
 Act 74 by Ted Miller on 6-25-1972, Recorded L. 1, P. 3. 12" BALSAM-SOUTH 35.3' P. POLE.)
 Survey by Ted Miller on 8-15-1975, Recorded L. 2, P. 108. FOUND 1½" PIPE (WIT. S32°W 40.7'
 Survey by R.S. Scott Assoc., on 4-28-1978, Recorded L. 3, P. 3. 10" CEDAR-S3°W 2.32' 9" BALS.)
 FOUND 1¼" PIPE & ½" BAR & CAP (WIT. SOUTH 12" BALSAM 2.1'-S32°W 10" CEDAR 40.7'- SOUTH
 POWER POLE 25.3')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-13) S. ¼ corner of Section 34, T 30 N, R 3 E.
 Found 1½" pipe with ½" rod & cap #12018.
 S 3* W Balsam stump 2.32'
 S 32* W Cedar stump 40.7'
 No evidence of original corner.

**SURVEY &
 REMONUMENTATION**

DEC 18 1995

COMMISSION


**APPROVED BY
 PEER GROUP**

JUN 02 95

LLB

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-13) S. ¼ corner Section 34, T 30 N, R 3 E.
 Set concrete monument & remonumentation cap. #18660
 N 20* W 8" Maple 79.9'
 N 60* E 9" Scotch Pine 77.0'
 S 50* W 11" Balsam 14.67'
 S 09* W Power Pole 35.65'
 20' South of centerline.
 Witnesses marked with a 30" penny spike & P.S. tag #18660.
 Approved by the Peer Group on June 2, 1995 as the best available evidence of the
 position of the original corner.



Signed by Donald E. Marlatt

Date 11-7-1995

Surveyor's Michigan License No. 18660