

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency (County)	Located In: AVERY TWP.	Corner Code -# L-13
1. Public Land Survey	T 30N R 3E	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-21-1995 13:23:40

A. PANGAN-MCELROY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald E. Marlatt, in a field survey on 4-24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(L-13) S. 1/4 corner of Section 36, T 30 N, R 3 E.
Post set by Lewis Clason.
N 08* E 6" Spruce 42 links
N 24* W 7" Spruce 40 links
MSHD witness by Norman Caldwell on 1-7-1965.
R.S. Scott Engineering Survey on 1-7-1975, Recorded L. 2, P. 37.

CALDWELL WIT. FOUND 4"X 4" POST & SET 3/4" PIPE.
N 6°E 75.16' 7" BALSAM
S73°E 28.26' 4" BALSAM
S30°E 22.09' 11" BALSAM (NBT)
ACT 74 BY L. BEAURF GARD
RECORDED L. 1, P. 120.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-13) S. 1/4 corner of Section 36, T 30 N, R 3 E.
Found concrete monument & cap #18654 & square cedar stake.
S 70* W 12" Spruce 29.21'
S 68* E 14" Spruce 28.4'
No evidence of original corner.

SURVEY &
REMONUMENTATION
DEC 18 1995
COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-1) N. 1/4 corner of Section 1, T 29 N, R 3 E.
Placed remonumentation cap on concrete monument. #18660
S 70* W 12" Spruce 29.21' (Existing)
N 48* E 12" Spruce 58.59'
S 85* E 16" Spruce 55.73'
S 68* E 14" Spruce 28.4' (Existing)
Witnesses marked with a 30" penny spike & P.S. tag #18660.
Approved by the Peer Group on June 2, 1995 as the best available evidence of the position of the original corner.

APPROVED BY
PEER GROUP

JUN 02 95

[Signature]

Signed by Donald E. Marlatt Date 7-11-1995
Surveyor's Michigan License No. 18660