

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 30 <sup>N.</sup> <sub>•</sub> , R. 4 <sub>•</sub> E.	D-1; E-1;
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	T. 30 <sup>N.</sup> <sub>•</sub> , R. 4 <sub>•</sub> E.	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <sub>•</sub> , R. _____ <sub>•</sub> E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JUNE 7, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-1 SET BY PROPORTIONATE MEASUREMENT, MIDPOINT ON LINE BETWEEN SECTION CORNERS. NO U.S. EVIDENCE:
- 1 SET CORNER BY STANDARD SURVEY PROCEDURE FOR THE SUBDIVISION OF SECTIONS.
- E-1 SET BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN N 1/4 SECTION 4 AND RESTORED NW CORNER SECTION 5. NO EVIDENCE OF PREVIOUS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>D-1</u>	<u>1</u>	<u>E-1</u>
SET DNR MONUMENT	5/8" ROD WITH CAP	DNR MONUMENT
12" CEDAR N42°E 12.8'	9" B. ASH S29°E 17.8'	14" TAMRACK N62°E 26.9'
18" CEDAR S89°W 40.1'	8" R. MAPLE S46°W 36.0'	10" TAMRACK S51°W 29.9'

SIGNED BY *Kenneth J. Ostling* DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. #10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ MONTMORENCY COUNTY