

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>30</u> N. <u>•</u> , R. <u>4</u> E. <u>•</u>		C-1; B-1; C-2; C-3
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JUNE 7, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX
 C. (CONTINUED)

C-3
 SET 5/8" ROD W/RLS CAP
 3" MAPLE S17°W 29.55'
 3" ASH S54°W 17.89'


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1 SET THIS CORNER AT U.S. RECORD MEASUREMENT FROM S 1/4 SECTION 31, AS REESTABLISHED. NO PREVIOUS CORNER EVIDENT.
- B-1 SET CORNER BY PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS, AT THE LATITUDE OF THE CORRECTION LINE.
- C-2 SET CORNER BY PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS. BEST EVIDENCE OF PROPER LOCATIONS FOR CORNER. FENCE CORNER IS ABOUT 30' N AND 67' W.
- C-3 SET THIS CORNER ON LINE OVER EXISTING CORNERS WEST AND SOUTH. NO PREVIOUS CORNER OR U.S. EVIDENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-1</u>	<u>B-1</u>	<u>C-2</u>
SET DNR MONUMENT	SET 5/8" X 36" IRON BAR	SET DNR MONUMENT
9" W. OAK S29°W 17.7'	W/CAP	5" MAPLE N46°E 19.6'
5" OAK N69°E 5.1'	7" CEDAR S70°W 18.2'	5" MAPLE N22°W 47.24'
	6" CEDAR S55°E 60.9'	

SIGNED BY *Kenneth J. Ostling* DATE 8/17/82
 SURVEYOR'S MICHIGAN REGISTRATION NO. #10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ MONTMORENCY COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET