

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency (County)	Located In:	Corner Code #
	Rust Township	H-1
1. Public Land Survey	T 30 N R 4 E	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

JUN 02 95 *AB*

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

09-22-1995 11:28:54

A. PANGAN-MCELROY
REGISTER OF DEEDS Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard, in a field survey on May 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No corner set on original survey.

1-1973, Mark Ennis, PORTER'S SURVEY, Found and accepted 3/4" pipe in road in line with fence to the South as the North 1/4 corner of Section 3. Witnesses marked: (N 25° E 72.08' Corner fence post) (East 65.45' 3/4" pipe in C/L of Road SE corner Sec. 33, T 31 N, R 4 E) (S 35° E 64.86' Power Pole) (South 32.71' Corner fence post).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe in Road as mentioned above. It is not known who set the pipe of Record.

SURVEY &
REMONUMENTATION

DEC 18 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

North 1/4 corner of Section 3, T 30 N, R 4 E

Replaced 3/4" pipe with 4" x 36" concrete monument and Montmorency County Remonumentation Cap P.S. #18654. Accepted as a careful and faithful establishment of the position of the corner. Approved by the Peer Group on June 2, 1995.

- N 18° E 48.12' 9" Norway (Placed 60d penny spike & P.S. tag #18654)
- N 25° E 80.80' 9" Norway (Placed 60d penny spike & P.S. tag #18654)
- N 60° E 46.90' Corner fence post (Placed P.K. nail & P.S. tag #18654)
- S 20° E 65.65' Power Pole (R) (Placed P.K. nail & P.S. tag #18654)
- East 65.43' Section corner of Sections 33 and 34, T 31 N, R 4 E. (4" x 36" conc. mon. & Remonumentation cap #18654)

Signed by Larry G. Beauregard Date 9/22/95
Surveyor's Michigan License No. 18654