

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Montmorency (County)	Located In:	Corner Code #
	Rust Township	
1. Public Land Survey	T 30 N R 4 E	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

09-22-1995 11:29:12

REGISTER OF DEEDS

I, Larry G. Beauregard, in a field survey on June 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

5-1840, Lewis Clason, Deputy Surveyor, Intersected third correction line. Witnesses marked: (S 10° E 66 links 12" Beech) (S 53° W 68 links 16" Beech).

No Date, Montmorency County Road Commission Records indicate that McQueen witnessed this corner with no date given. Witnesses: (S 64°-30' E 43.0' 10" Elm) (S 46°-45' W 45.12' 12" Elm).

1985, Donald E. Marlatt, P.S. #18660, Found 2" pipe buried 15" in ground. Witnesses marked: (S 40° W 44.89' 30" Elm) (S 60° E 48.95' Corner fence post). (East 68.65' Fnd. 2" pipe at South 1/4 corner of Sec. 34, T 31 N, R 4 E).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" pipe and witnesses mentioned above by Donald Marlatt.

SURVEY &
REMONUMENTATION

DEC 18 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Closing corner for Sections 2 and 3, T 30 N, R 4 E

Placed 4" diam., x 36" concrete monument and Montmorency County Remonumentation Cap P.S. #18654. Accepted as the best available evidence of the position of the original corner. Approved by the Peer Group on June 2, 1995.

- S 45° W 44.86' 36" Elm (R) (Placed blaze, 60d penny spike & P.S. tag #18654, typ)
- S 20° W 106.59' 4" Elm
- S 20° E 99.23' Power Pole (Placed P.K. nail & P.S. tag #18654)
- S 60° E 48.85' Corner fence post (Placed P.K. nail & P.S. tag #18654)
- East 68.68' S. 1/4 corner Sec. 34, T 31 N, R 4 E
- East 31.5' ± Centerline of Road, North and South

APPROVED BY
PEER GROUP
JUN 02 95

Signed by Larry G. Beauregard Date 9/22/95
Surveyor's Michigan License No. 18654