

✓

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

## LAND CORNER RECORD


MONTMORENCY COUNTY  
T 31 N R 1 E

DESCRIPTION OF CORNER NE corner Section 29

CORNER MONUMENT Set DNR Monument

DATE MONUMENT PLACED AND WITNESSED 9-7-72

WITNESSES TO CORNER..... 7" W. Birch S 89 W 19.8'



13" W. Birch S 51 E 19.8'

40" W. Pine Stp SOUTH 4.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set this corner on line between section corner South and restored Section Corner North, at double distance of South half mile between 28-29. This point is faced by a 30" W. Pine stump with three hack marks which we conclude to be a witness to this corner. No post or monument was located.



SIGNED Kenneth J. Ostling DATE 9-12-72  
REGISTERED LAND SURVEYOR 10058

DISTRIBUTION:

Forestry Division, Lansing