

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


MONTMORENCY COUNTY
T 31 N R 1 E

DESCRIPTION OF CORNER E 1/4 corner, Section 29

CORNER MONUMENT Set DNR Monument

DATE MONUMENT PLACED AND WITNESSED 9-7-72

WITNESSES TO CORNER.....



15" R. Oak N 46 E 67.9'


24" Tw. R. Pine N 16 W 110.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner set approximately in line with old fence line East, and in conformity with U.S. record to swamp edge and stream South, on line between Section corners 1/2 mile South and 1/4 miles North. This concurs with the GLO record, and appears to have been occupied at one time on the basis of this location. A 1/2" pipe located about 110' North appears to be a point of intersection for the road junction, and we can find no evidence it was intended as a corner.



SIGNED Kenneth J. Ostling DATE 9-12-72
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

Forestry Division, Lansing