

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Montmorency
COMMISSION
(County)

Located In: Vienna Twp Corner Code #

STATE OF MICHIGAN
MONTMORENCY COUNTY
Recorded & Filed

11-02-1994 15:44:42

A. PANGAN-MCELROY
REGISTER OF DEEDS

- 1. Public Land Survey T 31N R 1E (A-2)
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

APPROVED BY
PEER GROUP
AUG 0 5 94
[Signature]

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 15 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 18 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |

I, Larry G. Beauregard in a field survey on August, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(A-2) GLO marked Cedar 10" $\frac{3}{4}$ " post by John Mullett May 4, 1840.
No other wits marked.

G.F. DeLa Mater P.S. #693 in 1928 set $\frac{1}{2}$ " x 30" bar midway in line. Wits marked: (West 11.0' 15" Cedar stump); (S 10° E 5.0' 24" Cedar stump).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(A-2) Found $\frac{1}{2}$ " bar by G.F. DeLa Mater from 1928 survey Section 6, T 31 N, R 1 E, in line with fence line South. Replaced with a 4" x 36" concrete monument and a 3" diam., Aluminum cap #18654 marked Montmorency County Remonumentation corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(A-2) $\frac{1}{4}$ corner common to Sec. 6, T 31 N, R 1 E and Sec. 1, T 31 N, R 1 W
4" x 36" Concrete monument & Re-mon. cap. Accepted as a careful and faithful establishment of the position of the corner. Approved by the Peer Group on August 5, 1994.

- P. Pole N 30° E 36.35' -- Placed P.K. nail & P.S. tag #18654 in pole.
- 11" Birch S 45° E 29.31' -- 33'± South of Power line East and West.
- 12" Poplar N 75° E 19.48'
- 8" Tw. Poplar S 15° E 11.22'

Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 11/2/94
Surveyor's Michigan License No. 18654

