

**SURVEY & REMONUMENTATION**

**Montmorency County Remonumentation**

Liber **00012** Page **0113**

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

Montmorency Located In: Vienna Twp Corner Code #  
 (County)

1. Public Land Survey	T <u>31</u> N R <u>1E</u>	<u>(A-8)</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-02-1994 15:45:51

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**APPROVED BY PEER GROUP**

MAY 13 94

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Larry G. Beauregard in a field survey on August, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2								
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (A-8) GLO  $\frac{3}{4}$  Sec. post set by John Mullett May 4, 1840.  
Wits: Hemlock 16" S 70° E 18 links      Sugar 10" N 35° W 16 links
- G.F. DeLa Mater P.S. #693 in 1921 placed small piece of R.R. iron at corner midway in line. Wits: (7" Elm N 77° 27' 6" links).
- Bob Mitchell P.S. #28417 in 1992 set  $\frac{1}{2}$ " bar & cap over R.R. iron by G.F. DeLa Mater.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (A-8) Found  $\frac{1}{2}$ " bar & cap by Bob Mitchell over 6" R.R. iron 12" below surface by G.F. DeLa Mater. Replaced  $\frac{1}{2}$ " bar & R.R. iron with a 4" x 36" concrete monument and a 3" diam., Aluminum cap #18654 marked Montmorency County Remonumentation corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- (A-8)  $\frac{1}{4}$  corner common to Sections 19, T 31 N, R 1 E and Section 24, T 31 N, R 1 W.  
4" x 36" concrete monument & Re-mon. cap P.S. #18654. Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on May 13, 1994.

11" Cherry N 41° E 62.11'      7" Elm S 40° E 78.92'  
8" Apple S 58° E 90.49'      P. Pole S 10° W 79.93' - Placed P.K. nail & tag #18654

Placed blaze, 20 penny spike & P.S. tag #18654 (typ)

Signed by Larry G. Beauregard Date 11/2/94  
Surveyor's Michigan License No. 18654