

APR 24 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

STATE OF MICHIGAN  
MONTMORENCY COUNTY  
Recorded & Filed

11-02-1994 15:46:41

A. PANGAN-MCELROY  
REGISTER OF DEEDS

Montmorency (County)

Located In: Vienna Twp Corner Code ##

- 1. Public Land Survey T 31N R 1E (A-12)
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

APPROVED BY PEER GROUP

MAY 13 94

*[Signature]*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	8		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry G. Beauregard in a field survey on March 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-12) GLO ¼ Sec. post set by John Mullett May 4, 1840.

Wits: Maple 8" S 52° W 07 links Maple 8" N 22° E 10 links

Peter Chenard P.S. #14200 in 1974 set ½" X 24" bar & cap, wits marked: (N 30° E 13.42' Tw. 10" Oak) (East 47.80' Tw. 14" Oak) (S 50° E 15.46' 10" Oak) (S 65° W 23.16' Tw. 6" Oak)  
Note: Chenard set corner by proportional measure between Record corners North and South.

Carl R. Johnson P.S. #30083 DNR Surveyor in 1991 found ½" x 24" bar, cap & witnesses previously set by Peter Chenard in 1974.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-12) Fnd. ½" X 24" bar, cap & witnesses set by Peter Chenard in 1974.

(Re-placed P.S. cap with a 3" diameter aluminum cap marked Montmorency County Remonumentation Corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-12) ¼ Cor. Comm. to Sec. 31, T31N, R1W & Sec. 36, T31N, R1E

½" X 24" bar & Re-mon. cap #18654. Accepted as the best available evidence of the re-establishment of the original corner. Approved by the Peer Group on May 13, 1994.

N 50° E 13.35' Tw. 9" Oak West 22.92' Tw. 11" Oak  
S 80° E 47.65' Tw. 14" Oak S 30° E 15.47' Tw. 9" Oak

(Placed blaze, 20 penny spike & P.S. cap #18654) (typ)

Signed by Larry G. Beauregard  
Surveyor's Michigan License No. 18654

Date 11/2/94