

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>31</u> N. R. <u>3</u> E.	<u>G-11; G-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>31</u> N. R. <u>3</u> E.	<u>3; 13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Montmorency

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 17, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- G-11 Found 2" pipe from DeLaMater witnesses. G.F.D. had one O.B.T.
- G-12 Set corner from probable DeLaMater witness, which placed it in center of road and nearly in line with fence east.
- 3 Set by standard survey procedure.
- 13 Set by standard survey procedure for the subdivision of sections.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-11	G-12	3
2½' of 1" pipe (over 2" pipe)	DNR monument & N-S road	2½' of 1" pipe
7" Maple N80°W 26.4	14" Maple N40°E 44.2	4" R. Pine N40°E 80.6
6" R. Oak N08°W 74.9	1" W. Pine S84°E 70.2	7" Maple S83°E 44.4
Face of P. Pole N60°E 69.8	2" R. Pine N73°W 44.6	Top large stone S80°E 37.7
Conc. Mon. N56°E 57.9		
		13
		2½' of 1" pipe
		8" Cedar S74°E 18.0
		5" Maple S40°E 21.8


SIGNED BY Kenneth J. Ostling DATE 6/18/74

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ MONTMORENCY COUNTY