

Montmorency County Remonumentation

08147

Liber 12 Page 15

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 20 10 13 AM '93
A. PANISAN-MCELROY

For corners in

Montmorency (County) Located In: Corner Code #

1. Public Land Survey T 31N R 4E A-1 ✓
T 31N R 4E A-2

2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

APPROVED BY PEER GROUP
NOV 05 93

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
6		5		4		3		2		1		
7		8		9		10		11		12		
13		14		15		16		17		18		
19		20		21		22		23		24		
25		26		27		28		29		30		
31		32		33		34		35		36		

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-1) N.W. Cor. Sec. 6, T31N, R4E
Cor. set by Hiram Burnham 1850.
Aspen 10-S 35 W-43, Y. Pine 14-N 35 W-28
Land Cor. record by Ken Ostling 5-17-1966.
Survey by D.E. Porter 6-8-1981.
Survey by R.S. Scott Assoc. Inc. 11-27-1984.

(A-2) W. 1/4 Cor. Sec. 6, T31N, R4E
Cor. set by Hiram Burnham 1850.
Tamarack 12-S 59 W-39
Tamarack 14-N 18 W-22
Survey by D.E. Porter L. 3, P. 147.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-1) N.W. Cor. Sec. 6, T31N, R4E
Fnd. DNR Mon.
S 7° W 64.5' 10" Y. Pine
N 64° E 21.8' 5" J. Pine
N 68° W 11.8' 8" R. Oak

(A-2) W. 1/4 Cor. Sec. 6, T31N, R4E
Fnd. 1/2" rod & Sq. Cedar
N 30° W 12" Cedar 4.2'
S 8° W 11" Cedar 3.9'

No evidence of original corner. No evidence of original corner.

The Peer Group approved (A-1) as a perpetuation of the original government corner.
The Peer Group approved (A-2) as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-1) N.W. Cor. Sec. 6, T31N, R4E
DNR Mon.
N 60° W 12" Oak 11.50'
N 2° W 9" Oak 25.7'
N 30° E 14" Oak 45.0'
S 68° E 9" Oak 39.56'

(A-2) W. 1/4 Cor. Sec. 6, T31N, R4E
Placed Re-Mon cap on 1/2" rod.
N 79° W 9" Cedar 33.62'
N 30° W 12" Cedar 3.40'
S 35° E 12" Cedar 19.70'
S 8° W 11" Cedar 3.90'

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt Date Dec 15, 1993

Surveyor's Michigan License No. 18660

