

# Montmorency County Remonumentation

Liber 12 Page 16

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

08148

A. PANGAN-MCELROY

*Donald E. Marlatt*

DEC 20 10 13 AM '93

RECEIVED  
MONTMORENCY CITY  
REGISTER OF DEEDS

For corners in

<u>Montmorency</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>31N</u> R <u>4E</u>	<u>A-3</u> ✓	
	T <u>31N</u> R <u>4E</u>	<u>A-4</u>	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ R _____	<b>APPROVED BY PEER GROUP</b>	
	S _____ R _____		
3. Miscellaneous Property in Sec.	S _____ R _____		
	S _____ R _____		
	S _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Donald E. Marlatt, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |  |
|--|--|
| <p>(A-3) S.W. Cor. Sec. 6, T31N, R4E<br/>Post set by Hiram Burnham 1850.<br/>Dry Spruce Pine 8-N 2 W-3.79<br/>Green Spruce Pine 12-S 63 W-3.32<br/>D.E. Porter Survey L. 1, P. 11.<br/>Act 74 by Ronald Bischer L. 1, P. 275.<br/>D.E. Porter Survey L. 3, P. 147.</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T31N, R4E<br/>Post set by Hiram Burnham 1850.<br/>Cedar 9-S 51 W-15<br/>Cedar 10-N 59 E<br/>Act 74 by Ronald Bischer<br/>L. 1, P. 275.<br/>Survey by R.S. Scott Assoc. Inc.<br/>L. 2, P. 466.</p> |
|--|--|

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- |  |  |
|--|--|
| <p>(A-3) S.W. Cor. Sec. 6, T31N, R4E<br/>Fnd. 1" pipe &amp; wood post.<br/>West 327.60' conc. Mon.<br/>East 370.0' conc. Mon.<br/>South 826.39' conc. Mon.<br/>Falls in Marsh.</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T31N, R4E<br/>Fnd. conc. Mon. &amp; Sq. stake.<br/>N 50° E 7.22' 5" Spruce Pine<br/>S 45° E 10.32' 5" Spruce Pine<br/>S 25° W 17.07' 6" Cedar</p> |
|--|--|

No evidence of original corner.

No evidence of original corner.

The Peer Group approved (A-3) & (A-4) as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |   |
|--|---|
| <p>(A-3) S.W. Cor. Sec. 6, T31N, R4E<br/>Placed Re-Mon. cap &amp; ½" rod in 1" pipe.<br/>S 15° W 14" Poplar 279.15'<br/>West 327.60' conc. Mon.<br/>East 370.00' conc. Mon.<br/>South 826.39' conc. Mon.</p> | <p>(A-4) W. ¼ Cor. Sec. 7, T31N, R4E<br/>Set Re-Mon. cap on conc. Mon.<br/>S 50° W 12" Cedar 17.53'<br/>N 87° W 7" Spruce Pine 16.2'<br/>N 21° W 11" Spruce Pine 18.95'<br/>S 13° W 7" Spruce Pine 19.28'</p> |
|--|---|

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

