

MONTCORENCY COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
 MONTMORENCY COUNTY  
 REGISTER OF DEEDS  
 DEC 28 9 06 AM '93  
 A. PANGAR-NOELTROY

For corners in

Montmorency (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>4E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Larry G. Beauregard a field survey on August, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(A-9) GLO Cedar Post set by Hiram Burnham April 1850.  
 Wits: Aspen 12" S 30° W 13 links Aspen 14" N 55° W 8 links

NOTE: THIS TWP. LINE IS A RESURVEYED LINE BY BURNHAM.

Percy Beltz (Montmorency Co. Rd. Comm.) in 1941 fnd. Cor. & witnessed same with Conc. Mon's (N 45° W 50' Conc. Mon.) (S 45° E 50' Conc. Mon.).

Norman C. Caldwell P.S. #12018 in 1972 fnd. Conc. Mon. at corner. (Co. Rd. #487 Survey) Filed Act 74, Rec. L. 1, P. 24 Wits: (N 05° E 79.10' 8" Basswood) (N 50° W 50.4' Conc. Mon) (S 45° E 49.5' Conc. Mon.).

Duane R. MacNeill P.S. #19237 (Montmorency Co. Rd. Comm. Eng.) fnd. Mon. & wits & replaced Cor. with a 1" pipe in Mon. box after construction & paving of Co. Rd. #487 in 1989.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-9) Fnd. 1" pipe & P.S. cap #19237 in Mon. box on the C/L of Co. Rd. #487.  
 (Placed 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Cor. on same.)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-9) Sec. Cor. Comm. to Sec's 24, & 25, T31N, R3E & Sec's 19 & 30, T31N, R4E  
 1" pipe & Re-Mon cap #18654 in Mon. box. Accepted as the best available evidence of the original corner, approved by the Peer Group on September 24, 1993.  
 N 60° W 93.95' T. Pole N 75° E 140.60' T. Pole  
 S 15° W 39.78' Cor. Fe. Post North 32.70' Ex. bar & P.S. cap #27452

Signed by Larry G. Beauregard Date 12-27-93  
 Surveyor's Michigan License No. 18654