

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Montmorency</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>31N</u> R <u>4E</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 MONTMORENCY CITY
 REGISTER OF DEEDS
 Dec 28 9 07 AM '93
 A. PINEAK-HCELROY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Larry G. Beauregard in a field survey on August, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-10) GLO Post set by Hiram Burnham April 1850.
 Wits: Hemlock 10" N 60° W 9 links Hemlock 8" S 10° W 12 links
 NOTE: THIS TWP. LINE IS A RESURVEYED LINE BY BURNHAM.
 Donald E. Marlatt P.S. #18660 in 1984 set 1/2" bar & cap from witnesses fnd. at Montmorency Co. Rd. Comm. office. Wits fnd: (N 85° W 7" Cedar 17.6' (R) (S 38° W 13" Cedar 11.3' (R) NBT) (N 65° E 12" Cedar 20.1' (R) NBT) (12' South fe. Cor.).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-10) Fnd. 1/2" bar & cap #18660 & wits.
 Re-placed with Conc. Mon. & 3" dia. Aluminum cap marked Montmorency Co. Re-Mon. Corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-10) 1/4 Cor. Comm. to Sec's 25 & 30, T31N, R3E & T31N, R4E
 Conc. Mon. & Re-Mon. cap #18654, accepted as a reestablishment of the original corner, approved by the Peer Group on September 24, 1993.
 N 85° W 16.7' 7" Cedar (R) NBT N 65° E 20.1' 12" Cedar (R) NBT
 S 38° W 11.3' 13" Cedar (R) NBT South 12.0' Cor. fe. post
 (Placed 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93

Surveyor's Michigan License No. 18654