

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Montmorency (County), Located In, Corner Code #. Row 1: Public Land Survey, T 31N R 4E, A-11.

RECEIVED
MONTMORENCY CITY
REGISTER OF DEEDS
DEC 28 9 07 AM '93
A. FRANCIS-MCELROY

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (1,1) is shaded.

I, Larry G. Beauregard in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-11) GLO Post set by Hiram Burnham April 1850. Wits: Hemlock 24" S 15° W 16 links Hemlock 30" N 25° W 30 links
NOTE: THIS TWP. LINE IS A RESURVEYED LINE BY BURNHAM.
Carl R. Roser P.S. #12028 (MDOT Survey Chief) fnd. 1/2" pipe 8" above ground in 1965. (Alignment Survey for M-32 relocated.) Wits marked: (N 70° E 6" Oak 18.90') (S 65° W 4" Oak 31.01') (S 65° W 5" Oak 11.22').
Kenneth J. Ostling P.S. #10068 (DNR Surveyor) replaced 1/2" pipe with std. DNR Cor. in 1982. Filed Act 74, Rec. L. 1, P. 329. Wits marked: (12" R. Maple N 37° E 31.0') (5" R. Maple S 22° E 18.3')
Donald E. Marlatt P.S. #18660, in 1984 fnd. DNR cor., & marked wits: (N 20° E 10" Maple 30.86') (S 10° E 9" Birch 20.77').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-11) Fnd. DNR Mon. 1" x 3' pipe with 4" Aluminum cap #10068 set by Kenneth J. Ostling.



C. Description of monument for corner and accessories established to perpetuate locating the position of

(A-11) Sec. Cor. Comm. to Sec's 25 & 36, T31N, R3E & Sec's 30 & 31, T31N, R4E
Std. DNR Mon. P.S. #10068, accepted as the best available evidence of the position of the corner, approved by the Peer Group on September 24, 1993.
S 15° E 18.3' (R) 18.45' to spike S 62° E 20.77' (R) & (M) 12" Birch in Clump of 3
S 70° E 27.58' Tw. 12" Maples N 37° E 31.0' (R) 30.81' to spike 12" R. Maple
(Placed 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12-27-93
Surveyor's Michigan License No. 18654